

Projektuesi: Bashkia Kucove

Objekti: Rikualifikimi i rrugeve Brisqe-Dajko-Ismail
Qemali-Sul Bega-Mafuz Laze

Datë: 15-10-2025

PREVENTIV

NR	KODI	EMËRTIMI I PUNIMEVE	NJËSIA	SASIA	ÇMIMI	VLEFTA
		1. PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m³, ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	250.0		
		Shuma 1:				
		2. PUNIME SHITESASH				
2	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	7000.0		
3	3.212/b	Shtrese stabilizant t=10cm	m2	7920.0		
		Shuma 2:				
		3. ANALIZA TEKNIKE				
4	3.233/4	Shtrese asfaltobetoni me zall lavatrice, 7cm, me makineri	m2	6600.0		
		Shuma 3:				
		4. PUNIME BETONI E BETONARMEJE				
5	3.244	Struktura monolite betoni C 20/25	m3	20.0		
		Shuma 4:				
		5. PUNIME HEKUR BETONI				
6	2.166	F.V. Hekur betoni periodik Ø 6 - 10 mm	ton	1.0		
7	2.166/1a	F.V. Hekur betoni periodik Ø > 12 mm	ton	1.0		
		Shuma 5:				
		6. PUNIME BETONI DHE B/A				
8	2.202	Themel e xokol butobetoni C16/20	m3	15.0		
9	2.112	Mure buto betoni C 12/15	m3	34.0		
		Shuma 6:				

Shuma Analiza	22,912,350.00
Fondi Rezervë (0.0%)	0.00
Shuma Analiza + Fondi Rezervë (0.0%)	22,912,350.00
TVSH (20%)	4,582,470.00
Shuma me TVSH	27,494,820.00
Totali	27,494,820.00

Preventivuesi:

Bashkia Kucove



Shënime:

