

PREVENTIV

Objekti: “Ndërtim banese rrezik shëmbjeje, lagjia Fetanaj, Ngjeqar”

Nr	Nr.An.	Lloji i punimeve	Njësia	Sasia
1.PUNIME NDERTIMI				
1	An	Germim dheu me krah	m ³	21.6
2	An	Betonim plinti	m ³	4.5
3	An	Themel buto Betoni	m ³	10.8
4	An	Kollona b/a	m ³	1.98
5	An	Brez b/a C 16/20, h ~ 8 m	m ³	6.12
6	An	Arkitrare mbi hapësirat e dyer-dritareve	m ³	1.8
7	An	F V hekur betoni periodik	ton	1.08
8	An	Mur blloku t=20cm	m ³	28.8
9	An	Ndërtim cati vendi me tjegulla marseleze	m ²	97.2
10	An	Tavane rrjet teli + suva	m ²	59.4
11	An	Porte e madhe	m ²	3.24
12	An	Dritare D/alumini	m ²	6.84
13	An	Dyer D/alumini	m ²	10.8
14	An	Shtrese Betoni	m ³	5.94
15	An	Mermer për dyer-dritare	m ²	5.4
16	An	Shtrese dysHEMEJE me pllaka	m ²	63
17	An	Veshje banjo me pllaka majolike	m ²	10.8
18	An	Suvatim brenda	m ²	198
19	An	Nenshtrese Zhavorri	m ³	6.3

SHUMA 1

2.PUNIME ELEKTRIKE				
1	An	F.V. Tub elektrik plastmasi 18-26	ml	120
2	An	F.V. Percjelles Ø 4mm	ml	120
3	An	F.V. Percjelles Ø 2.5mm	ml	90
4	An	F V Celesa dhe priza 10A me nulifikim	copë	9
5	An	F.V. Portollampa	copë	5
6	An	F.V. Automat kryesor me 24 vende	copë	1
7	An	F.V. Kuader ndricimi	copë	1
8	An	F.V. Siguresa 25A	copë	6
9	An	F.V. Kuti derivacioni plastike	copë	4